



Telephones:
Off.(PBX) : 0184-2291119,
: 2291519, 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ren.nic.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

2789-2815

REGISTERED

No.P-2(92)K/Misc Nain Farm /11-12

Dated: 20 August 2011

M/S Incharge

OR Computer/Cell

For publication

B. K. K.
23/08/11

Sub:- Cleaning jungle and earth work in excavation and banking for earthen roads at CSSRI, experimental farm, Nain, Panipat.


Dear Sirs,

You are hereby invited to submit the rates for the works on the above subject as per details attached and as per terms & conditions below. Quotations should be sealed. Unsealed quotations are liable to be rejected. The sealed quotations giving reference of work on the body of envelope as per guidelines in the letter of invitation must reach at this Institute on or before **12 September, 2011** in the name of Sr. Admn. Officer, CSSRI, Karnal – 132 001 (Haryana).

TERMS & CONDITIONS:

- 1 After completion of the work, the work site & its surroundings should be cleared and cleaned immediately.
- 2 Any type of official implements and help will not be provided by the Office.
- 3 All precautionary safety measures to be followed & risk if any to be born by the contractor. Office will not be responsible for any mis-happening if caused during the execution of work to the contractor or his workers.

4. T.D.S as per rules (prevailing at the time) will be deducted from your Bill.
5. The payment will be made on the basis of actual measurement/work done and only on bill basis after completion of works.
6. **The quotations must be accompanied with EMD for Rs. ~~₹2000/-~~ ^{4300/-} in The form of Bank Draft drawn in favour of ICAR-UNIT-CSSRI, Karnal. If EMD is not found attached, the quotation will not be entertained.**
7. The work must be completed within **45 days** from the date of the issue of work order. A penalty may be imposed as per GFR ^{rule} in case the work is not completed within stipulated time.
8. The rates for scheduled items must be quoted for all items in terms of % above, below or at par on the basis of DSR-2007 and for the Non Scheduled items local rates may be quoted for each items.
9. Director, CSSRI, Karnal has the right to reject the quotations without assigning any reason.
10. **PAN No. Name of Bank and Account No. must be written on the quotation otherwise it would be cancelled.**
11. The latest attested copies of his PAN No, Licence Contractorship must also be attached.
12. The quotation may also be read on this Institute web. Site www.cssri.org.
13. The work may be executed in consultation with Dr. R.K.Yadav, P.S and Incharge CSSRI Nain Farm, Panipat.


20/8/11

ASSTT. ADMN. OFFICER

Encl: As above

Sub Estimate for clearing jungle and earth work in excavation and banking for earthen roads at experimental Farm in Village Nain (On the basis of DSR 2007).

Item No.	DSR 2007	Description of Item	Qty.	Unit	Rate	Amount (Rs.)
----------	----------	---------------------	------	------	------	--------------

EARTHWORK

1	2.31	Clearing jungle including, uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared of 50 m outside the periphery of the area cleared. (for 672 m length with width of 65 feet (19.81 m) (15 feet wide road and 25 feet on each side of road for excavation of earth and banking for road)	13312.32	sqmt		
---	------	--	----------	------	--	--

2	2.3	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with 1/2 tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m				
	2.3.1	All kinds of soil				1500.00 cum

Add Cost weightage Index on DSR 2007 @

(Rupees ~~XXXXXXXXXXXX~~)

Assumptions considered in the Estimate

The earth for banking of roads to be excavated from the adjoining field area

The water for watering and ramming of earthen road to be managed in tankers by the contractor

The proposed earthen road with specifications

Length = 672 m or 2204 feet

Width = 3.66 m or 12 feet

Height (Compacted) = 0.61 m or 2 feet

Volume = 1500.31 cum