



Telephones:
Off.(PBX) : 0184-2291119,
: 2291519 , 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ren.nic.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

REGISTERED

No.P-2(93)K/Misc. Work/11-12

Dated: 3 October 2011

M/S OIC (Computer Cell)

for Publication

Sub:- Renovation of room in old tractor garage.

Dear Sirs,


You are hereby re- invited to submit the rates for the works on the above subject as per details attached and as per terms & conditions below. Quotations should be sealed. Unsealed quotations are liable to be rejected. The sealed quotations giving reference of work on the body of envelope as per guidelines in the letter of invitation must reach at this Institute on or before

25 October, 2011 in the name of Sr. Admn. Officer, CSSRI, Karnal – 132 001 (Haryana).

TERMS & CONDITIONS:

- 1 After completion of the work, the work site & its surroundings should be cleared and cleaned immediately.
- 2 Any type of official implements and help will not be provided by the Office.
- 3 All precautionary safety measures to be followed & risk if any to be born by the contractor. Office will not be responsible for any mis-happening if caused during the execution of work to the contractor or his workers.

4. The water charges and Electricity charges will be deducted as per norms.
5. T.D.S as per rules (prevailing at the time) will be deducted from your Bill.
6. The payment will be made on the basis of actual measurement/work done and only on bill basis after completion of works.
7. **The quotations must be accompanied with EMD for Rs.600/- in the form of Bank Draft drawn in favour of ICAR-UNIT-CSSRI, Karnal. If EMD is not found attached, the quotation will not be entertained.**
8. The work must be completed within **45 daya** from the date of the issue of work order. A penalty may be imposed as per GFR in case the work is not completed within stipulated time.
9. The rates for scheduled items must be quoted for all items in terms of % above, below or at par on the basis of DSR-2007 and for the Non Scheduled items local rates may be quoted for each items.
10. Director, CSSRI, Karnal has the right to reject the quotations without assigning any reason.
11. **PAN No. Name of Bank and Account No. must be written on the quotation otherwise it would be cancelled.**
12. The latest attested copies of his PAN No, Licence Contractorship must also be Attached.



ASSTT. ADMN. OFFICER

Encl: As above

Sub: Estimate and specification: for the Renovation of Room in old Tractor Garage *(on the basis of S&R 2077)*

Sl.No.	Description of Item	Qty.	Rate per unit	Amount (in Rs.)
1.	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:5:2:1 1:3:6 or richer mix.	3 cum.		
2.	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.78 cum.		
3.	Centering and Shuttering including strutting, propping, etc and removal of form for: 5.9.4 Shelves (cast in situ)	3 sqm.		
4.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position	50 kg		
5.	And binding all complete: 5.22.3 Cold twisted bars. Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron And 3mm M.S. gusset plate at the junction and corners, all necessary fittings complete.	2.7 sqm		
6.	including priming coat of approved steel primor: 3 Cement concrete flooring: 1:2:4 finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.	20 sqm.		
7.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:	2 cum		
8.	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) 12 mm cement plaster of mix:	20 sqm		
9.	13.1.1 1:4 (1 cement : 4 fine sand) 15 mm cement plaster on the rough side of single or half brick wall of mix:	20 sqm		
10.	13.2.2 1:6 (1 cement : 6 fine sand) White-washing with lime to give an even shade: 13.37.1 New work (three or more coats)	85 sqm		

11. Painting with acid proof paint of approved brand and manufacture of required colour to give an even shade. 10 sqm
12. 13:64:1 Two or more coats on new work.
Pointing on tile brick work with cement mortar 1:3:1 cement : 3 fine sand): 30 sqm
13.32.1 Flush/Ruled/Struck or weathered pointing