



Telephones:
Off.(PBX) : 0184-2291119,
: 2291519, 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ernet.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

Sr. OIC (Computer) SK Wame
27.10.2011
Datta 28/10

REGISTERED
No.P-2(100)K/Lib /11-12 /4589-4611
Dated: 27 October, 2011

M/S _____

OIC Computer Cell
CSSRI, Karnal
*for publication
in website*

Sub:- Renovation of Library flooring, painting on walls at CSSRI, Karnal

Dear Sirs,

You are hereby invited to submit the rates for the works on the above subject as per details attached and as per terms & conditions below. Quotations should be sealed. Unsealed quotations are liable to be rejected. The sealed quotations giving reference of work on the body of envelope as per guidelines in the letter of invitation must reach at this Institute on or before

16 November, 2011 in the name of Sr. Admn. Officer, CSSRI, Karnal – 132 001 (Haryana).

TERMS & CONDITIONS:

- 1 After completion of the work, the work site & its surroundings should be cleared and cleaned immediately.
- 2 Any type of official implements and help will not be provided by the Office.
- 3 All precautionary safety measures to be followed & risk, if any to be born by the contractor. Office will not be responsible for any mis-happening if caused during the execution of work to the contractor or his workers.
4. The water charges and Electricity charges will be deducted as per norms.
5. T.D.S as per rules (prevailing at the time) will be deducted from your Bill.

- 6 The payment will be made on the basis of actual measurement/work done and only on bill basis after completion of works.
- 7 **The quotations must be accompanied with EMD for Rs.6,200/- (Rupees Six thousand two hundred only)- in the form of Bank Draft drawn in favour of ICAR-UNIT-CSSRI, Karnal. If EMD is not found attached, the quotation will not be entertained.**
- 8 The work must be completed within **45 days** from the date of the issue of work order. A penalty may be imposed as per GFR in case the work is not completed within stipulated time.
- 9 The rates for scheduled items must be quoted for all items in terms of % above, below or at par on the basis of DSR-2007 and for the Non Scheduled items local rates may be quoted for each items.
- 10 Director, CSSRI, Karnal has the right to reject the quotations without assigning any reason.
- 11 **PAN No., Name of Bank and Account No. must be written on the quotation otherwise it would be cancelled.**
- 12 The latest attested copies of his PAN No, Licence of Contractorship must also be attached.



ASSTT. ADMN. OFFICER

Encl: As above

name of work : Estimate for Renovation of Library flooring and painting on walls :

Item No.	DSR No.	Description of Item	Qty.	Unit	Rate	Amount
1	11.78.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorptions less than 0.08% and conforming to Is: 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete				
2	11.78.2 14.46	Size of Tile 60x60 cm Removing dry or oil bound distemper , water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	150.00 800.00	sqm sqm		
3	13.26	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete	800.00	sqm		
4	13.41	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade	800.00	sqm		
5	13.41.2 14.54	New work (two or more coats) over and including priming coat with cement primer Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade:				
	14.54.1	One or more coats on old work.	130.00	sqm		
Sub-Total						
1	NSR	Hacking of existing floor with sharp tool distance not more than 100 mm c/c both sides for laying the floor tile on it including applying of cement slurry @ 1.10 qts/100 sqmts etc. complete as per the direction of Engineer-In-Charge.tile floor o ot	150	Sqm		
	NSR	Removing the existing doors and refixing after proper cutting as per actual size required.	4	No.		