



Telephones:
Off.(PBX) : 0184-2291119,
: 2291519 , 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ernet.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

*OIC (computer) cell.
Sh. K. Mehta
27.10.2011
B. Mehta
28/10*

REGISTERED

No.P-2(1)K/Misc. Works /11-12/4612-34
Dated: 27 October, 2011

M/S

OIC Computer Cell
CSSRI, Karnal

for publications in web site

Sub:- Replacement of windows (Type A,B&C) and doors in residential quarters at CSSRI, Karnal

Dear Sirs,

You are hereby invited to submit the rates for the works on the above subject as per details attached and as per terms & conditions below. Quotations should be sealed. Unsealed quotations are liable to be rejected. The sealed quotations giving reference of work on the body of envelope as per guidelines in the letter of invitation must reach at this Institute on or before **16 November, 2011** in the name of Sr. Admn. Officer, CSSRI, Karnal – 132 001 (Haryana).

TERMS & CONDITIONS:

- 1 After completion of the work, the work site & its surroundings should be cleared and cleaned immediately.
- 2 Any type of official implements and help will not be provided by the Office.
- 3 All precautionary safety measures to be followed & risk, if any to be born by the contractor. Office will not be responsible for any mis-happening if caused during the execution of work to the contractor or his workers.
4. The water charges and Electricity charges will be deducted as per norms.

5. T.D.S as per rules (prevailing at the time) will be deducted from your Bill.
6. The payment will be made on the basis of actual measurement/work done and only on bill basis after completion of works.
7. **The quotations must be accompanied with EMD for Rs.4,600- (Rupees Four thousand and six hundred only) in the form of Bank Draft drawn in favour of ICAR-UNIT-CSSRI Karnal. If EMD is not found attached, the quotation will not be entertained.**
8. The work must be completed within **45 days** from the date of the issue of work order. A penalty may be imposed as per GFR in case the work is not completed within stipulated time.
9. The rates for scheduled items must be quoted for all items in terms of % above, below or at par on the basis of DSR-2007 and for the Non Scheduled items local rates may be quoted for each items.
10. Director, CSSRI, Karnal has the right to reject the quotations without assigning any reason.
11. **PAN No., Name of Bank and Account No. must be written on the quotation otherwise it would be cancelled.**
12. The latest attested copies of his PAN No, Licence of Contractorship must also be attached.



ASSTT. ADMN. OFFICER

Encl: As above

Work : Estimate for replacement of Windows (Type A, B & C) and doors in residential quarters

DSR/07 Item No.	Description of Item	Qty.	Unit	Rate	Amount
1 (a)	15.12 Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowknats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area 3 sq. metres and below	142.00	each		
2	9.1 Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position : Sal wood	0.183	cum		
4	9.1.2, 9.7 Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick Ply wood 7 ply, 9 mm thick	9.41	sqm		
5	9.9 Decorative plywood one side decorative veneer and commercial veneer on other face (Type 1) confirming to IS 1328 BWR Type. Providing and fixing glazed shutters for doors, windows and clerestory windows using 10 kg/sqm. (4 mm thick) glass panes including black enamelled ISI marked M.S butt hinges with necessary screws.	86.40	sqm		
6	9.9.2 9.9.2.2 9.2.7 Kiln seasoned and chemically treated hollock wood. 30mm thick shutters Providing and fixing 35mm thick wire gauze shutters using galvanised M.S. wire gauze of average width of aperture 1.4mm with wire of dia. 0.63 mm for doors, windows and clerestory windows including ISI marked bright finished or/and black enamelled M.S. butt hinges with necessary screws :	8.30	sqm		
7	9.2.7.2 9.5.3 Kiln seasoned and chemically treated Hollock wood. Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 mix (1cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size)	132.00	each		
3	9.96 Providing and fixing aluminium sliding door bolts ISI anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete: 250x16 mm	56.00	each		
3	9.96.2 9.97 Providing and fixing aluminium tower bolts ISI anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with nuts and screws etc. complete: 250x10 mm	284.00	each		
10	9.97.2 9.1.00 Providing and fixing aluminium handles ISI marked anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 125 mm	149.00	each		
12	9.100.1 13.5 Applying priming coat :				

3.50.1	With ready mixed pink or grey primer of approved brand and manufacture on wood work (hard and soft wood)	216.15	sqm
13.61	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :		
13.61.1	Two or more coats on new work	129.15	sqm
14	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under including cutting the patch in proper shape and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground within 50 metres lead		
14.1.1	With cement mortar 1:4 (1 cement : 4 fine sand)	15.00	sqm
13.40	Distemping with dry distemper of approved brand and manufacture (two or more coats) and of required shade over and including priming coat of whitening to give an even shade.	15.00	sqm

(say)